

**Schedule of Rates - Goshen Sports Centre 2020-21**

<b>Ref</b>	<b>Description</b>	<b>Quantity</b>
<b>S200</b>	<b><u>SITE CLEARANCE</u></b>	
1	Take down and remove to tip off Site metal wire mesh fence 3600mm high	264
2	Take down and remove to tip off Site timber post and rail fence 450mm high	38
3	Take up and remove to tip off Site precast concrete flag (600mm x 600mm)	42
4	Take up and remove to tip off Site litter bin	1
5	Take up and remove to tip off Site shrubbery as per site photograph GSC005	12
<b>S300</b>	<b><u>FENCING</u></b>	
1	Timber Diamond rail fencing 450mm high with timber posts and mild steel straps as per standard detail drawing H109	38
<b>S600</b>	<b><u>EARTHWORKS</u></b>	
1	Excavation of unacceptable material	13
2	Extra Over for excavation in Concrete	6
3	Disposal of material	13
4	Backfilling of foundation cavities 150mm diameter exceeding one metre but not exceeding two metres of cover to formation level with acceptable material	133
5	Imported topsoil Class 5B	60
6	Topsoiling 200mm thick to surfaces sloping 25° to the horizontal	540
<b>S2700</b>	<b><u>DAYWORKS</u></b>	
1	Allow the Provisional Sum of £1,000 for the basic cost of labour, plant and materials (PROVISIONAL)	
2	% adjustment to be added to the basic cost of labour, plant and materials (PROVISIONAL)	
<b>S3000</b>	<b><u>LANDSCAPE AND ECOLOGY</u></b>	
1	Grass seeding to surfaces sloping at 10° or less to the horizontal	54

**TOT**

<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
lin m	7.50	£ 1,980.00
lin m	5.00	£ 190.00
m <sup>2</sup>	7.50	£ 315.00
Item	25.00	£ 25.00
No	28.00	£ 336.00
lin m	30.00	£ 1,140.00
m <sup>3</sup>	12.00	£ 156.00
m <sup>3</sup>	35.00	£ 210.00
m <sup>3</sup>	45.00	£ 585.00
No	12.50	£ 1,662.50
m <sup>3</sup>	55.00	£ 3,300.00
m <sup>2</sup>	1.25	£ 675.00
Item	1000.00	£ 1,000.00
Item	5.00	£ 50.00
m <sup>2</sup>	2.00	£ 108.00
<b>TOTAL OF TENDER</b>		<b>£ 11,732.50</b>